

# HAZARDOUS MATERIALS SURVEY AND 2023 REASSESSMENT 40 STEWART STREET, OTTAWA, ON



Project No.: Z2021101HZ / CCC-230252-00

Prepared for:

University of Ottawa

Prepared by:

McIntosh Perry Limited (MPL)

MPL Contact:

John Tufts, Project Manager

Hazardous Materials / Environmental Health & Safety

T: 613836-2184 E: [j.tufts@mcintoshperry.com](mailto:j.tufts@mcintoshperry.com)

Date:

X date, 2023

McINTOSH PERRY

## TABLE OF CONTENTS

REASSESSMENT SURVEY 2023.....	I
EXECUTIVE SUMMARY .....	I
1.0 INTRODUCTION .....	1
2.0 PROPERTY DESCRIPTION .....	2
3.0 FINDINGS & RECOMMENDATIONS.....	2
<i>Designated Substances</i> .....	2
3.1 <i>Asbestos</i> .....	2
3.1.1 Fireproofing.....	4
3.1.2 Mechanical Pipe Insulation .....	4
3.1.3 Flexible Duct Connector .....	4
3.1.4 Heat Shield or Heat Shield Insulation .....	5
3.1.5 Texture Finishes.....	5
3.1.6 Plaster .....	5
3.1.7 Drywall Joint Compound .....	5
3.1.8 Ceiling Tiles.....	5
3.1.9 Vinyl Floor Tiles.....	5
3.1.10 Vinyl Sheet Floor.....	5
3.1.11 Brick/Stone Mortar .....	5
3.1.12 Concrete Block Mortar .....	5
3.1.13 Ceramic Wall / Floor Tile Grout .....	5
3.1.14 Transite (Asbestos Cement) .....	6
3.1.15 Caulking.....	6
3.1.16 Cementitious Coating.....	6
3.1.17 Mastic.....	6
3.1.18 Fire Doors .....	6
3.1.19 Roofing Material .....	6
3.2 <i>Lead</i> .....	7
3.2.1 Paint Finishes.....	7

---

3.2.2	Battery Packs .....	8
3.3	Mercury.....	9
3.3.1	Thermostat Switches.....	9
3.3.2	Fluorescent Light Tubes .....	9
3.3.3	Pressure Gauges and Float Switches.....	9
3.4	Silica.....	10
	<i>Other Hazardous Materials</i> .....	10
3.5	Polychlorinated Biphenyls (PCBs) .....	10
3.5.1	Light Ballasts .....	10
3.5.2	Transformers.....	11
3.6	Ozone Depleting-Substances (ODSs) and Other Halocarbon .....	11
3.7	Radioactive Materials .....	11
3.8	Underground and Above Ground Storage Tanks (USTs and ASTs) .....	12
3.9	Mould.....	12
3.9.1	Mould .....	12
3.9.2	Water Damage.....	12
<b>4.0</b>	<b>GENERAL CONSIDERATIONS AND LIMITATIONS .....</b>	<b>13</b>
	Appendix A – Regulatory Requirements	
	Appendix B – Survey Methodology & Background Information	
	Appendix C – Laboratory Certificate of Analysis	
	Appendix D– Site Photographs	
	Appendix E – Asbestos Containing Materials Checklist	
	Appendix F – Hazardous Containing Materials Checklist	
	Appendix G – Site Sampling & Location Plans	

## **REASSESSMENT SURVEY 2023**

**This building is unoccupied and has been since the previous reassessment in 2022. There are no changes to the quantity, condition or location of any previously identified Hazardous Building Materials, including asbestos.**

## EXECUTIVE SUMMARY

McIntosh Perry Limited (**MPL**) was retained by the University of Ottawa to complete a hazardous materials survey for the building located at 40 Stewart Street in Ottawa, Ontario. The survey was conducted on February 14<sup>th</sup>, 2020. **The Reassessment Survey was conducted on x date, 2023.**

The purpose of the survey was to determine the presence of building materials containing Designated Substances and other hazardous materials, as defined under the Ontario Occupational Health and Safety Act. Designated Substances are eleven chemical agents prescribed under Ontario Regulation 490/09. In addition, a visual assessment was conducted for the presence of polychlorinated biphenyls (PCBs), radioactive materials, ozone depleting-substances (ODSs), other halocarbons and mould.

Based on the assessment conducted by MPL, the following asbestos-containing materials (ACMs) were identified or suspected to be present in the building:

**Table A: Summary of Asbestos-Containing Materials Identified**

Material Description	Friable?	Location	Type of Asbestos
Duct Paper Insulation	Yes	Specific Areas Only	Chrysotile
Mastic/Adhesive	No	Specific Areas Only	Chrysotile
Brick/Stone Mortar	-	Throughout the Building	Suspected

**Note: Please refer to the complete report for specific details and recommendations.**

All repairs or removal of asbestos-containing materials must be conducted according to Ontario Regulation 278/05, Regulation respecting Asbestos on Construction Projects and in Buildings and Repair Operations - made under the Occupational Health and Safety Act. Asbestos-containing waste must also be handled and disposed of according to Ontario Regulation 347/90 as amended – made under the Environmental Protection Act. Any suspect building materials encountered that were not assessed as part of this survey should be assumed to contain asbestos until proven otherwise by analytical testing;

Sub-trades working with or in close proximity to ACMs should be informed of their presence;

Given that ACMs have been identified and will likely remain in place, an Asbestos Management Plan is required, and an ACMs inventory must be kept on site. All ACMs must be routinely inspected to ensure no damage has occurred, and the inventory must be updated once in each 12-month period and as may be required based on expected changing site conditions, abatement and/or renovation activities.

Based on the assessment conducted by MPL, the following Designated Substances and Hazardous Materials were identified or suspected to be present in the building:

**Table B: Summary of Designated Substances & Hazardous Materials Identified**

Material Description	Location
Lead Paint	Throughout Building
Lead Acid Batteries	Specific Areas Only
Mercury Vapour	Specific Equipment
Silica	Throughout Building
Ozone Depleting-substances	Throughout Building
Radioactive Materials	Specific Equipment
Above-ground Storage Tank	Specific Equipment

**Note: Please refer to the complete report for specific details and recommendations.**

Designated Substances area regulated under Ontario Regulation 490/09 — Designated Substances, made under the Ontario Health and Safety Act, which applies to controlling designated substances in the workplace.

In addition to Ontario Regulation 490/09, the following guidelines must also be adhered to when conducting work activities that involve disturbance of the materials mentioned above:

- Guideline: Lead on Construction Projects, issued April 2011 by the Occupational Health and Safety branch of the Ministry of Labour.
- Guideline: Silica on Construction Projects issued April 2011 by the Occupational Health and Safety branch of the Ministry of Labour.
- Environmental Abatement Council of Canada (EACC) Mould Abatement Guidelines.

Prior to any renovations or demolition activities within the building, designated substances and hazardous materials must be decommissioned by a licensed contractor such that they are contained and not released to the environment during decommissioning as per O. Reg. 347/09- made under the Environmental Protection Act.

Any suspect building materials encountered that were not assessed as part of this survey, should be assumed to contain designated substances or hazardous materials until proven otherwise by analytical testing.

This report should be made available to contractors tendering on any renovation or demolition work. In turn, all contractors requesting tenders from subcontractors shall furnish this report to subcontractors.

**This executive summary is not to be used alone. This report should be reviewed in its entirety.**

X date, 2023

**University of Ottawa**  
141 Louis-Pasteur Private  
Ottawa, Ontario  
K1N 1E3

via email: [martine.bergeron@uottawa.ca](mailto:martine.bergeron@uottawa.ca)

Attention: Martine Bergeron, Senior Specialist, Occupational Health and Safety

Re: 40 Stewart Street in Ottawa, Ontario  
Hazardous Materials Survey and 2023 Reassessment  
McIntosh Perry Limited Reference No. Z2021101HZ / CCC-230252-00

---

## 1.0 INTRODUCTION

In accordance with your instructions, McIntosh Perry Limited (MPL) carried out a Hazardous Materials Survey at the building located at 40 Stewart Street in Ottawa, Ontario. The site is situated at the southwest corner of Stewart Street and Cumberland Street. The survey of the building was conducted on February 14, 2020. **The Reassessment Survey was conducted on x date, 2023.**

The purpose of the survey was to determine the presence of building materials containing Designated Substances and other hazardous materials, as defined under the Ontario Occupational Health and Safety Act. Designated Substances are eleven chemical agents prescribed under Ontario Regulation 490/09. In addition, a visual assessment was conducted for the presence of polychlorinated biphenyls (PCBs), radioactive materials, ozone depleting-substances (ODSs), other halocarbons and mould.

MPL completed the following,

- Visual review of the building to identify materials which could contain Designated Substances and hazardous materials;
- Bulk sampling and analysis of building materials suspected of containing asbestos (if required);
- Bulk sampling and analysis of representative paints and finishes suspected of containing lead (if required);
- Review of previously completed Hazardous Materials Survey(s) and historical building record(s); and,
- Recommendations for appropriate action where required.

## 2.0 PROPERTY DESCRIPTION

The subject building is a 2 ½ storey was constructed circa 1900 and covers approximately 2,971 square feet. The subject building was a former residential building converted to institutional use. The subject building was observed to be constructed with a stone and mortar foundation with one basement level, wood-frame construction with brick cladding, and an asphalt shingle roof. The interior walls were gypsum wallboard and plaster. Throughout the subject building, ceilings were observed to be predominantly plaster. The floors were generally Vinyl Sheet Flooring or carpet over wood.

## 3.0 FINDINGS & RECOMMENDATIONS

### Designated Substances

### 3.1 Asbestos

#### Findings

A total of thirty-five (35) bulk samples were collected during the survey and sent to an accredited laboratory for analysis. A summary of potential asbestos-containing samples collected along with the sample location, type and friability are presented in Table 1.

The Laboratory Certificate of Analysis for asbestos are included in Appendix C.

**Table 1.1:**  
**Asbestos Laboratory Results**

Sample ID	Location	Material	Type and Content	Friability
1.1	Room 103	Carpet Mastic (Yellow)	None Detected	N/A
1.2	Room 103	Carpet Mastic (Yellow)	None Detected	N/A
1.3	Room 103	Carpet Mastic (Yellow)	None Detected	N/A
2.1	Room B01	Mastic (Black)	10% Chrysotile	Non-Friable
2.2	Room B01	Mastic (Black)	Stop Positive - Not Analyzed	Non-Friable
2.3	Room B01	Mastic (Black)	Stop Positive - Not Analyzed	Non-Friable
3.1	Room 203	VSF (Green)	None Detected	N/A
		Mastic (Beige)	None Detected	N/A
3.2	Room 203	VSF (Green)	None Detected	N/A
		Mastic (Beige)	None Detected	N/A
3.3	Room 203	VSF (Green)	None Detected	N/A



Sample ID	Location	Material	Type and Content	Friability
		Mastic (Beige)	None Detected	N/A
4.1	Room 105	Drywall Joint Compound	None Detected	N/A
4.2	Room 206	Drywall Joint Compound	None Detected	N/A
4.3	Room 206	Drywall Joint Compound	None Detected	N/A
		Plaster Layer (White)	None Detected	N/A
4.4	Room 203A	Drywall Joint Compound	None Detected	N/A
4.5	Room 201	Drywall Joint Compound	None Detected	N/A
		Plaster (Skim Coat)	None Detected	N/A
		Plaster (Base Coat)	None Detected	N/A
5.1	Room 103	Plaster (Skim Coat)	None Detected	N/A
		Plaster (Base Coat)	None Detected	N/A
5.2	Room 105	Plaster (Skim Coat)	None Detected	N/A
		Plaster (Base Coat)	None Detected	N/A
5.3	Room 204	Plaster (Skim Coat)	None Detected	N/A
		Plaster (Base Coat)	None Detected	N/A
5.4	Room 202A	Plaster	None Detected	N/A
5.5	Room 203A	Plaster (Skim Coat)	None Detected	N/A
		Plaster (Base Coat)	None Detected	N/A
5.6	Room 201A	Joint Compound	None Detected	N/A
		Plaster (Skim Coat)	None Detected	N/A
		Plaster (Base Coat)	None Detected	N/A
5.7	Room 205	Joint Compound	None Detected	N/A
		Plaster (Skim Coat)	None Detected	N/A
		Plaster (Base Coat)	None Detected	N/A

N/A – Not Applicable

VSF – Vinyl Sheet Flooring

Stop Positive – Material considered to be asbestos-containing as per O. Reg. 278/05.

**Table 1.2 (2022):**  
**Asbestos Laboratory Results**

Sample ID	Location	Material	Type and Content	Friability
40STE 1.1	Basement	Paper Duct Insulation	65% Chrysotile	Friable
40STE 1.2	Basement	Paper Duct Insulation	Stop Positive - Not Analyzed	Friable

Sample ID	Location	Material	Type and Content	Friability
40STE 1.3	Basement	Paper Duct Insulation	Stop Positive - Not Analyzed	Friable

Stop Positive – Material considered to be asbestos-containing as per O. Reg. 278/05.

Please refer to Appendix E – Asbestos-Containing Materials Checklist for material conditions, quantities (where applicable), and recommended actions.

The following building materials (if present) were investigated for asbestos content,

### **3.1.1 Fireproofing**

No fireproofing was observed throughout the subject building.

### **3.1.2 Mechanical Pipe Insulation**

#### *3.1.2.1 Mechanical Pipe Straight Insulation*

No mechanical pipe straight insulation was observed throughout the subject building.

#### *3.1.2.2 Mechanical Piping Elbows/Fittings Insulation*

No mechanical pipe elbows/fittings insulation was observed throughout the subject building.

#### *3.1.2.3 Mechanical Piping Hangers Insulation*

No mechanical pipe hanger insulation was observed throughout the subject building.

#### *3.1.2.4 HVAC Duct Insulation*

No HVAC duct insulation was observed throughout the subject building.

#### *3.1.2.5 Other Mechanical Insulation*

Duct Insulation Paper was observed throughout the subject building's Basement (Room 01)subject building. The laboratory analytical results of samples collected from the basement during the 2022 Reassessment indicate that this material **contains 10% Chrysotile asbestos. This material is considered to be friable and was observed to be in fair condition during the 2022 Reassessment.**

### **3.1.3 Flexible Duct Connector**

No flexible duct connectors were observed throughout the subject building.

#### **3.1.4 Heat Shield or Heat Shield Insulation**

No potential asbestos-containing heat shield insulation was observed throughout the subject building.

#### **3.1.5 Texture Finishes**

No texture coat finishes were observed throughout the subject building.

#### **3.1.6 Plaster**

Ceiling/Wall plaster was observed throughout the subject building. The laboratory analytical results of ceiling/wall plaster samples collected throughout the building indicate that this material does not contain asbestos.

#### **3.1.7 Drywall Joint Compound**

A drywall joint compound was observed throughout the subject building. The laboratory analytical results of drywall joint compound samples collected throughout the building indicate that this material does not contain asbestos.

#### **3.1.8 Ceiling Tiles**

No suspended ceiling tiles were observed throughout the subject building.

#### **3.1.9 Vinyl Floor Tiles**

No vinyl floor tiles were observed throughout the subject building.

#### **3.1.10 Vinyl Sheet Floor**

Vinyl Sheet Flooring (Blue/Green) was observed in Rooms 203, 203A, and 203C. The laboratory analytical results of the Vinyl Sheet Flooring samples collected from Room 203C indicate that this material does not contain asbestos. The associated mastic (Beige) was also found not to contain asbestos.

#### **3.1.11 Brick/Stone Mortar**

To avoid damage and compromising the structure's integrity, no bulk samples of the brick/stone mortar were collected. Prior to renovation/demolition, brick mortar should be examined and tested for asbestos content. Brick/stone mortar should therefore be considered to contain asbestos until bulk samples and analysis until proven otherwise.

#### **3.1.12 Concrete Block Mortar**

No concrete block mortar was observed throughout the subject building.

#### **3.1.13 Ceramic Wall / Floor Tile Grout**

No ceramic wall/floor tile grout was observed throughout the subject building.

#### 3.1.14 *Transite (Asbestos Cement)*

No transite materials were observed throughout the subject building.

#### 3.1.15 *Caulking*

No potential asbestos-containing caulking was observed throughout the subject building.

#### 3.1.16 *Cementitious Coating*

No potential asbestos-containing cementitious coating finishes were observed throughout the subject building.

#### 3.1.17 *Mastic*

Mastic (black) was observed on plywood window coverings in the basement of the subject building (room B1). The laboratory analytical results of samples collected from the basement window indicate that this material **contains 10% Chrysotile asbestos**. This material is considered to be non-friable and was observed in fair condition.

#### 3.1.18 *Fire Doors*

No fire doors were observed at the subject building.

#### 3.1.19 *Roofing Material*

Roofing material (Shingles & Tar) was previously sampled in the subject building. The laboratory analytical results indicated that these materials do not contain asbestos.

#### *Recommendations*

- Materials identified to contain asbestos that are in good condition and do not pose a risk to workers or occupants can be managed in place. Prior to renovation/demolition activities that may disturb the ACMs, these materials must be removed following appropriate Type 1/2/3 asbestos abatement work procedures as detailed in O. Reg. 278/05 and disposed of as asbestos waste under O. Reg. 347;
- Please refer to Appendix E – Asbestos-Containing Materials Checklist for material conditions, quantities (where applicable), and recommended actions;
- Prior to renovation/demolition of materials which are assumed to be asbestos-containing (suspect materials which were not sampled, i.e., brick/stone mortar), these materials must either be tested for asbestos content or removed following appropriate asbestos abatement work procedures (Type 1/2/3) as detailed in O. Reg. 278/05 and disposed of as asbestos waste under O. Reg. 347;
- All repairs or removal of asbestos-containing materials must be conducted according to Ontario Regulation 278/05, Regulation respecting Asbestos on Construction Projects and in Buildings and Repair Operations - made under the Occupational Health and Safety Act. Asbestos-containing waste must also be handled and disposed of according to Ontario Regulation 347/90 as amended – made

under the Environmental Protection Act. Any suspect building materials encountered that were not assessed as part of this survey, should be assumed to contain asbestos until proven otherwise by analytical testing;

- Sub-trades working with or in close proximity to ACMs should be informed of their presence; and
- Given that ACMs have been identified and will likely remain in place, an Asbestos Management Plan is required, and an inventory of ACMs must be kept on site. All ACMs must be routinely inspected to ensure no damage has occurred, and the inventory must be updated once in each 12-month period and as may be required based on expected changing site conditions, abatement and/or renovation activities.

## 3.2 Lead

### Findings

#### 3.2.1 Paint Finishes

A total of seven (7) paint samples from the subject building were collected and analyzed for lead content. Results of bulk sampling testing, including testing previously completed by others, are summarized in Table 2, and the Laboratory Certificate of Analysis can be found in Appendix C.

**Table 2:**  
**Lead Sampling Locations and Laboratory Results**

Sample I.D.	Location	Material	Colour	Lead Concentration Weight by Conc. (%)
PB1	Room 101	Door Paint	Green	0.12%
PB2	Room 206	Door Frame Paint	Dark Green	22%
PB3	Room 203C	Wall Paint	Light Blue	0.12%
PB4	Room 206	Wall Paint	Light Green	7.7%
PB5	Room 105	Wall Paint	White	0.2%
PB6	Room 102	Ceiling Paint	Beige	5.4%
PB7	Exterior Porch	Porch Wood	Grey	10%
<b>Previously Identified Lead Paint Finishes</b>				
LBP-01	Exterior Porch	Porch Paint	Grey	16%
LBP-02	Room 105	Wall Paint	White	0.08
LBP-03	Room 103	Doorframe Paint	Dark Green	<0.05%
LBP-04	Room 100	Door Paint	Green	<0.02%
LBP-05	Room 101	Ceiling Paint	Beige	<0.07%
LBP-06	Room 206	Wall Paint	Light Green	4.5%

The paint finishes highlighted in blue in the above table was determined to contain low concentrations of lead, which are less than or equal to 0.1%. These paint finishes were observed to be in good condition, except for select areas that were observed in poor condition.

The paint finishes highlighted in pink in the above table are considered lead-containing paints or surface coatings with concentrations greater than 0.1% lead by weight. These paint finishes were observed to be in good condition, except for the porch, which was observed in poor condition.

All remaining paints tested were below the laboratory limit of detection for lead. However, all other paints throughout the subject building that are not mentioned in this report must be considered to be lead-containing unless sampling and analysis until proven otherwise.

The Laboratory Certificate of Analysis for the paint sample is also included in Appendix C.

### **3.2.2 Battery Packs**

Lead-containing acid battery packs were identified throughout the subject building. These battery packs were observed on walls and above exits throughout the surveyed building.

Lead may also be present in the following materials in the building:

- Solder used on copper domestic water lines;
- Solder used in bell fittings for cast iron pipes;
- Solder used in electrical equipment;
- Ceramic tile glaze; and
- Concrete and mortar products, etc.

### **Recommendations**

Paints identified to contain lead that is in poor condition must be immediately repaired and/or stabilized following a minimum Type 1/2 lead abatement procedures as per OMOL “Lead on Construction Project” dated April 2011.

Paints identified to contain lead that are in fair condition should be either repaired (where possible) and/or closely monitored for signs of further deterioration.

Paints identified to contain lead that are in good condition and do not pose a risk to workers or occupants can be managed in place.

Detailed worker protection protocols are outlined in the OMOL Guideline “Lead on Construction Projects” dated April 2011. Generally, removing the lead-based paint using a chemical gel or paste or a power tool equipped with a HEPA filter is considered a Type 1 operation. Removing lead-based paint by scraping or sanding using non-powered hand tools is considered a Type 2 operation. The removal of lead-based paint using abrasive blasting or power tools without a HEPA filter is considered a Type 3 operation and requires the most stringent worker protection protocols (similar to asbestos); Furthermore, high temperature cutting or welding would

also require Type 3 Operations under the Guideline for Lead on Construction Projects. If this type of work is required, it may be prudent to chemically remove the lead paint in selected locations prior to performing any high temperature cutting or welding.

All removed lead materials must follow the Ministry of Labour and Environmental Abatement Council of Canada Lead Guidelines.

Please refer to Appendix F – Hazardous Materials Checklist for material conditions, quantities (where applicable), and recommended actions.

Precautions should be taken as required during major renovations and demolition projects to ensure that workers' exposure levels to airborne lead do not exceed 0.05 mg/m<sup>3</sup>. This can be achieved by:

- providing workers with proper training;
- providing the workers with respiratory protection;
- wetting the surface of the materials to prevent dust emissions; and,
- providing workers with hygiene facilities to properly wash prior to exiting the work area.

Sub-trades working with or in close proximity to lead-based paint should be informed of its presence.

All waste material must be handled and disposed of according to the Revised Regulation of Ontario 347/90 as amended – made under the Environmental Protection Act. Lead waste generated may also be subject to the Leachate Criteria (Schedule 4) of this regulation.

### **3.3 Mercury**

#### *Findings*

##### **3.3.1 Thermostat Switches**

No thermostats containing liquid mercury were observed throughout the subject building.

##### **3.3.2 Fluorescent Light Tubes**

Fluorescent light fixtures were identified throughout the surveyed area containing 2 to 4 tubes per fixture. Mercury is likely to be present in vapour form in fluorescent light tubes.

##### **3.3.3 Pressure Gauges and Float Switches**

MPL did not identify pressure gauges containing liquid mercury throughout the subject building. MPL did not identify suspected float switches that may contain liquid mercury throughout the subject building.

#### *Recommendations*

Please refer to Appendix F – Hazardous Materials Checklist for equipment conditions, quantities (where applicable), and recommended actions.

Precautions must be taken to prevent mercury liquid/vapours from becoming airborne during building demolition. Mercury exposure is regulated under Ontario Regulation 490/09, Designated Substances - made under the Occupational Health and Safety Act." Prior to renovations to the building, all mercury-containing fluorescent light tubes, thermostats, and equipment must be removed and stored in a safe, secure location and/or properly disposed of in accordance with R.R.O. 1990, Regulation 347 General – Waste Management, made under the Environmental Protection Act.

### **3.4 Silica**

#### *Findings*

Silica is expected to be present in building materials such as concrete, brick, mortar and ceramic tiles throughout the structures. Free crystalline silica ( $\alpha$ -Quartz) may be a component in ceiling tiles and gypsum board. Silica (including free crystalline silica) may also be a component of concrete and brick surfaces noted in the building.

#### *Recommendations*

Please refer to Appendix F – Hazardous Materials Checklist for equipment conditions, quantities (where applicable), and recommended actions.

Precautions should be taken as required during major renovations and demolition projects on concrete (i.e. coring through concrete slabs, masonry demolition, etc.) to ensure that workers' exposure levels to airborne silica do not exceed 0.05 mg/m<sup>3</sup>.

This can be achieved by:

- providing workers with proper training;
- providing the workers with respiratory protection;
- wetting the surface of the materials to prevent dust emissions; and,
- providing workers with facilities to properly wash prior to exiting the work area.

Demolition work likely to impact silica-containing materials should be carried out per the requirement detailed in the Ontario Ministry of Labour document entitled "Guideline: Silica on Construction Projects," dated April 2011.

### **Other Hazardous Materials**

### **3.5 Polychlorinated Biphenyls (PCBs)**

#### *Findings*

#### **3.5.1 Light Ballasts**

The subject building is illuminated by LED and fluorescent lights. The representative ballasts in the building were assessed, and these ballasts were identified as non-PCBs content.



### **3.5.2 Transformers**

No PCBs containing electrical transformers were observed throughout the subject building. Transformers that could be assessed were observed to be dry-type and manufactured by Hammond Manufacturing.

#### *Recommendations*

Since no PCB-containing equipment was observed or suspected to be present during the site survey, no further action is required.

## **3.6 Ozone Depleting-Substances (ODSs) and Other Halocarbon**

#### *Findings*

A visual assessment for equipment potentially containing ODSs and other halocarbons was conducted. MPL observed equipment such as refrigerators and air conditions which contain or are suspected of containing ODSs or other halocarbons.

#### *Recommendations*

Please refer to Appendix F – Hazardous Materials Checklist for equipment conditions, approximate quantities (where applicable), and recommended actions.

Under the management of a licensed contractor, equipment containing R-134a does not represent a significant threat to human health or the environment; however, a licensed contractor must decommission equipment such that CFCs are contained and not released to the environment during servicing or operation.

## **3.7 Radioactive Materials**

#### *Findings*

A visual assessment of the subject building was conducted to determine if any electrical components containing radioactive materials were present. Smoke detectors were observed in Room 206, which contain small quantities of radioactive material.

#### *Recommendations*

Please refer to Appendix F – Hazardous Materials Checklist for equipment conditions, quantities (where applicable), and recommended actions.

The radioactive sources in smoke alarms are sealed and contained within a metal case inside the smoke detector and must not be damaged or tampered with. These materials do not pose a hazard as long as they remain contained and properly disposed of at the time of removal or replacement.

Prior to any renovations or demolition of the building, all equipment containing radioactive materials must be decommissioned by a licensed contractor such that radioactive materials are contained and not released to the environment during decommissioning as per O.Reg. 347/09.

### 3.8 Underground and Above Ground Storage Tanks (USTs and ASTs)

#### *Findings*

A visual survey of the subject building was conducted to determine if any USTs and ASTs were present. Two (2) ASTs were observed to be present in the basement of the surveyed area.

#### *Recommendations*

Please refer to Appendix F – Hazardous Materials Checklist for equipment conditions, quantities (where applicable), and recommended actions.

Prior to any demolition in the buildings throughout the facility, all USTs and ASTs equipment must be decommissioned by a licensed contractor such that substances are contained and not released into the environment during decommissioning.

### 3.9 Mould

#### *Findings*

#### *3.9.1 Mould*

A visual survey of the subject building was conducted to determine if any mould was present. No mould growth was identified in any areas throughout the subject site.

#### *3.9.2 Water Damage*

A visual survey of the subject building was conducted to determine if water damage was present. MPL did not identify any materials affected by water damage.

#### *Recommendations*

No further action is required since mould/water-damaged materials were not observed during the site survey.

**This report should be made available to contractors tendering on any renovation or demolition work. In turn, all contractors requesting tenders from subcontractors shall furnish this report to subcontractors.**

## 4.0 GENERAL CONSIDERATIONS AND LIMITATIONS

The information presented in this report is based on information provided by others, direct visual observation made by personnel with **McIntosh Perry Limited (MPL)**, and the results of laboratory testing as identified herein.

It should be noted that there might be hazardous materials in locations not visible during our investigation. In the event such material is encountered during demolition operations in the building, this material should be tested and dealt with accordingly.

The findings detailed in this report are based upon the information available at the time of preparation of the report. No investigative method eliminates the possibility of obtaining imprecise or incomplete information. Professional judgement was exercised in gathering and analyzing the information obtained and in the formulation of our conclusions and recommendations.

MPL does not certify or warrant the environmental status of the property nor the building on the property.

Please note that the passage of time affects the information provided in the report. Environmental conditions of a site can change. Opinions relating to the site conditions are based upon information that existed at the time that the conclusions were formulated.

The client expressly agrees that it has entered into this agreement with MPL, both on its own behalf and as agent on behalf of its employees and principals.

The client expressly agrees that MPL's employees and principals shall have no personal liability to the client in respect of a claim, whether in contract, tort and/or any other cause of action in law. Accordingly, the client expressly agrees that it will bring no proceedings and take no action in any court of law against any of MPL's employees or principals in their personal capacity.

We trust that we have detailed our findings clearly and that we have satisfactorily addressed the scope of work you require at this time. In the event you wish us to review our findings with you, or require our services further in this regard, please do not hesitate to contact our office.

Yours truly,

**MCINTOSH PERRY LIMITED**

Jane Zhang, M.Sc.  
Hazardous Materials, EH&S Technician  
Hazardous Materials/ Environmental Health & Safety



John Tufts, B.Sc.  
Project Manager  
Hazardous Materials/ Environmental Health & Safety

# **APPENDIX A**

## **Regulatory Requirements**

## REGULATORY REQUIREMENTS

In Ontario, there is a total of eleven Designated Substances. These substances have been regulated under Ontario Regulation 490/09 — *Designated Substances*, made under the Ontario Health and Safety Act, which applies to controlling designated substances in the workplace.

In addition to the Ontario Regulation 490/09 noted above, the following were observed for this survey:

Guideline: Lead on Construction Projects, issued April 2011 by the Occupational Health and Safety branch of the Ministry of Labour

Guideline: Silica on Construction Projects issued on April 2011 by the Occupational Health and Safety branch of the Ministry of Labour.

The Occupational Health and Safety Act (OHSA), R.S.O. 1990, c.0.1, s.30 (1) specifies that: “Before beginning a project, the owner shall determine whether any Designated Substances are present at the project site and shall prepare a list of all Designated Substances that are present at the site.

Section 30 of The Act requires that the list of Designated Substances be provided to prospective contractors and subcontractors who may do work on a site and come into contact at the site with Designated Substances.

The Ministry of Labour has designated the following substances:

- Acrylonitrile
- Arsenic
- Asbestos
- Benzene
- Coke Oven Emissions
- Ethylene Oxide
- Isocyanates
- Lead
- Mercury
- Silica
- Vinyl Chloride

Ontario Regulation 278/05 (O. Reg. 278/05), the Regulation respecting Asbestos on Construction Projects and in Buildings and Repair Operations, made under the Occupational Health and Safety Act (OHSA), requires owners of a building to identify asbestos-containing materials (ACMs) prior to potential disturbance of the materials.

In addition, an owner of a building is required to have an Asbestos Management Plan if ACMs (friable or non-friable) are present in the building and are to remain in place. An inventory of ACMs must be kept on site. All ACMs must be routinely inspected to ensure no damage has occurred, and the inventory must be updated once in each 12-month period and as may be required based on expected changing site conditions, abatement and/or renovation activities. Removal of all ACMs is required prior to building demolition.

In addition to the Designated Substances, the building was also surveyed for the presence of other hazardous materials such as polychlorinated biphenyls (PCBs), radioactive materials, ozone-depleting substances (ODSs), other halocarbons, and mould.

We understand that this survey has been conducted to comply with the regulatory requirements of Ontario Regulation 278/05.

## **APPENDIX B**

### **Survey Methodology & Background Information**

## **SURVEY METHODOLOGY**

For the purpose of this survey, not all Designated Substances or suspect hazardous materials were sampled. Selective sampling was carried out only for substances that were suspected to be present or those deemed to have a likely source of origin in the survey areas.

Materials that were homogeneous in nature and/or similar in appearance to other materials tested were considered to be of similar composition. The likelihood of ACMs being present in inaccessible areas, such as above gypsum board ceilings or behind gypsum wallboards, was determined by assessing the presence of asbestos-containing systems in adjacent areas. Equipment such as boilers, motors, blowers, electrical panels, fire doors, etc., must be de-energized or disassembled to examine internal components or materials. These items should be considered to contain hazardous materials until proven otherwise.

During the survey, representative samples of suspect building materials were collected and sent to CALA accredited independent laboratory for analysis. The Laboratory Certificate of Analysis is attached in Appendix C.

Other potential hazardous materials were identified by visual observation and/or by reviewing Material Safety Data Sheets (MSDS) and/or safety labels where available.

### **Investigated Areas**

The survey included all accessible areas and ceiling space within 40 Stewart Street, as required under our scope of work. No destructive investigations were performed as part of this survey. Photographs of the areas investigated can be found in Appendix D.

The assessment was directed at the interior structure and finishes of the building. It did not consider current or past owner or occupant articles throughout the building (i.e. contents, furniture, etc.) and did not report on possible contaminants in the soil under and surrounding the building or contents of vessels, drums, etc., that may be concealed.

### **Sampling and Assessment Methodologies**

Sampling was conducted as part of this assessment. Results for asbestos and lead samples can be found in the Findings & Recommendation Section 3.0.

A historical review of previous designated substance survey reports and abatement reports were examined as part of this survey. The reports are listed as follows,

- Designated Substance Report by CM3 Environmental (dated October 2017, reference # TLW 1561);

### **Asbestos**

#### *Background Information on Asbestos*

Asbestos is a generic name that has been given to a group of naturally occurring fibrous minerals. In the past, asbestos was commonly used as a component in building materials such as insulation, fireproofing and acoustic



or decorative panels. Although there are many types of asbestos, Ontario's three main forms of commercial importance are chrysotile, amosite and crocidolite.

An ACM is defined by O. Reg. 278/05 as a material that contains 0.5% or more asbestos by dry weight. ACMs are placed into two general classes, “friable” and “non-friable” ACMs. Friable ACMs are dry materials that can be crumbled, pulverized and reduced to powder by hand pressure. Typical friable ACMs include acoustical or decorative texture coats, fireproofing and thermal insulation. Non-friable ACMs are much more durable as they are held together by a binder such as cement, vinyl or asphalt. Typical non-friable ACMs include floor tiles, fire blankets, roofing materials and cementitious products such as wallboards, pipes or siding.

It has been recognized that hazardous situations may exist in buildings where ACMs are found. This is especially true where asbestos fibres may become airborne due to material ageing, physical damage, water damage or air movement.

In contrast, there is little reason for concern if the asbestos is in good condition, has not been damaged and is not in a location where it is likely to be disturbed.

### *Asbestos Survey Methodology*

The asbestos survey included identifying potential friable and non-friable asbestos-containing materials throughout the surveyed areas of the subject building.

The likelihood of ACMs being present in inaccessible areas, such as above gypsum wallboard ceilings and walls, was determined by assessing the presence of asbestos-containing materials in adjacent areas.

Fibreglass insulation was not submitted for analysis as it can be identified visually as non-asbestos material.

Building materials suspected of containing asbestos were identified, and representative sampling and laboratory testing of these materials was conducted. The number of bulk material samples collected from a homogeneous area was in accordance with Table 1. O. Reg. 278/05 s. 3 (3) below. Building materials suspected of containing asbestos were collected using wetting techniques and hand-sampling tools.

**Table 1 - O. Reg. 278/05 s. 3(3): Minimum Asbestos Bulk Material Sample Requirements**

<b>Item</b>	<b>Type of material</b>	<b>Size of the area of homogeneous material</b>	<b>Minimum number of bulk material samples to be collected</b>
1.	Surfacing material, including, without limitation, material that is applied to surfaces by spraying, troweling or otherwise, such as acoustical plaster on ceilings and fireproofing materials on structural members	Less than 90 square metres	3
		90 or more square metres but less than 450 square metres	5
		450 or more square metres	7
2.	Thermal insulation, except as described in item 3	any size	3

3.	Thermal insulation patch	Less than 2 linear metres or 0.5 square metres	1
4.	Other material	Any size	3

Preliminary identification of the samples was made using polarized light microscopy (PLM), confirming the presence and type of asbestos made by dispersion staining optical microscopy. This analytical procedure follows the U.S. Environmental Protection Agency Test Method EPA/600/R-93/116 Method for the Determination of Asbestos in Bulk Building Materials, June 1993.

EMSL Canada Inc. (EMSL), an independent laboratory, analyzed all bulk samples for asbestos content. EMSL is an independent laboratory accredited by the National Institute of Standards and Technology/National Voluntary Laboratory Accreditation (NIST/NVLAP) (Lab Code #200877-0).

Vinyl floor tiles were analyzed using the phase light microscopy (PLM) analysis method. However, given the composition of vinyl floor products, the PLM analysis method may be prone to yield false negative analytical results. Therefore, prior to removal or replacement, vinyl floor products previously identified to be negative should undergo additional analysis by Transmission Electron Microscopy (TEM) to confirm asbestos content, if any.

Materials identified to contain asbestos were assessed on the relative possibility of fibre release into the air due to a combination of their condition and accessibility.

#### *Evaluation of ACMs Based on Condition*

In evaluating an ACM's condition, the following criteria were applied:

- **Good** – Material shows no signs of damage and/or is encapsulated. ACM could remain in place until eventual building demolition or major renovation.
- **Fair** – Material shows signs of minor damage (<5% damage) or otherwise near the end of useful life. This includes minor shrinking, cracking, delamination and/ or other damage. The material should be monitored closely and scheduled to be repaired, encapsulated or removed.
- **Poor** – Damage is greater than 5% to any ACM material and is highly recommended to be removed, repaired or encapsulated.

*Note: The above evaluation criteria were also applied to other hazardous materials. Please refer to the Asbestos and Hazardous Materials Checklist in Appendix E & F for further details.*

## **Lead**

### *Background Information on Lead*

Lead was a common additive in exterior and hard-wearing paint applications. Lead was used to prolong the paint's shelf life and increase its flexibility and durability to wear and weather. Acute exposure to lead by inhalation or ingestion may cause headaches, fatigue, nausea, abdominal cramps and joint pain. Chronic exposures can cause reduced hemoglobin production and reduced lifespan. It has also been known to impact

the body's central and peripheral nervous systems and brain function and has been linked to learning disabilities in children.

Currently, no regulatory limit in Ontario determines what lead concentration constitutes a "lead-containing material." On October 21, 2010, Health Canada, under the *Hazardous Products Act*, stated that the lead content in surface-coating materials, furniture, toys and other articles for children should not exceed 90 mg/kg (0.009%, 90 ppm). However, this is intended for the importation or sale of products within Canada. Therefore, this is not to be misconstrued as a limit established to define a lead-containing material or a limit with respect to lead on construction projects.

The Environmental Abatement Council of Canada (EACC) has also developed the "*Lead Guideline for Construction, Renovation, Maintenance or Repair*" dated October 2014, which discusses the classification, handling, disturbance and removal of lead-containing materials. For the purpose of this guideline, paints or surface coatings containing less than or equal to 0.1% lead by weight (1000 mg/kg or 1000 ppm) are considered low-level lead paints or surface coatings. If these materials (and their respective surfaces) are disturbed in a non-aggressive manner and performed using adequate dust control procedures, then worker protection from the inhalation of lead is not required.

Furthermore, paints or surface coatings containing greater than 0.1% lead by weight are considered lead-containing paints or surface coatings. If these materials (and their respective surfaces) are disturbed, appropriate lead abatement procedures must always be followed.

Exposure to lead-containing materials is regulated under Ontario Regulation 490/09, *Designated Substances* - made under the Occupational Health and Safety Act. Care must be taken to prevent lead-containing particles from becoming airborne during the disturbance of lead-containing surfaces (i.e., during renovation or demolition projects). All lead abatement work must follow procedures outlined in the Guideline Lead on Construction Projects, issued in September 2004 (amended in April 2011) by the Occupational Health and Safety branch of the Ministry of Labour (Type 1-3). Similarly, the lead abatement work procedures outlined in the EACC Lead Guideline for Construction, Renovation, Maintenance or Repair (October 2014) may also be implemented (Class 1-3).

Lead has been used in solder on copper plumbing fixtures, lead conduit pipes, lead-calcium battery plates, ammunition, and nuclear and X-ray shielding devices. However, these materials were not sampled during this investigation but were noted where applicable.

Representative bulk samples of paint and finishes suspected of containing lead were collected to verify lead content in paints. Bulk samples were scraped down to the building base structure, with all possible layers present, placed in sealed plastic bags and labelled, and then submitted to an independent laboratory for analysis. Samples were treated with a dilute nitric acid sample digestion prior to filtration. The analysis utilized for lead detection in filtered samples was inductively coupled plasma optical emission spectrometry (ICP-OES).

## Mercury

### *Background Information on Mercury*

Mercury is known to cause poisoning in humans through inhaling vapours, ingesting contaminated materials or skin absorption through direct contact with the liquid.

Precautions must be taken to prevent mercury vapours from becoming airborne during renovations or building demolition. Exposure to airborne mercury is regulated under the Revised O. Reg. 490/09 as amended – Regulation respecting Mercury – made under the Occupational Health and Safety Act; and under O. Reg. 558, which amended O. Reg. 347/90 (General - Waste Management), mercury is classified as a Schedule 2(b) Hazardous Waste Chemical. Its hazardous waste number is U151.

Mercury is found in thermostats, temperature and pressure gauges, fluorescent lamps and batteries. Mercury in products can be released to the environment through breakage or disposal at the end of a useful life. Improper disposal of these mercury products poses a health and environmental risk to everyone. In addition, the disposal of mercury-containing products can create wastes that are often classified as hazardous. Wastes that leach mercury in concentrations exceeding Ontario Regulation 347/90 (General - Waste Management) limits are also considered hazardous.

The mercury in thermostats switch contains approximately 3-4 grams of mercury in a glass ampoule, typically attached to a metal coil. Mercury-containing switches have been used in thermostats for over 40 years.

Mercury is an essential component in fluorescent lamps and HID lamps. The mercury is in a vapour form, and the phosphor coating is on the lamp tube. Estimates of the mercury content contained in compact, 4-foot, and 8-foot lamps are 10 mg, 23 mg, and 46 mg, respectively.

Most fluorescent lamps qualify as hazardous waste when removed from service and are prohibited from disposal in the solid waste stream. Fluorescent lamps would be classified as 146T on your facility Generator Registration Report under O. Reg. 347/90 - General Waste Management, as amended by O. Reg. 558/00. Under this regulation, if the leachate results exceed 0.1 milligrams of mercury per litre for a given waste, the facility must treat the waste as hazardous. Most fluorescent and HID lamps will exceed the leachate toxicity limit; therefore, these wastes must be registered and treated as hazardous waste or sent for recycling.

## Silica

### *Background Information on Silica*

Silica is expected to be present in building materials such as concrete, brick, mortar and ceramic tiles throughout the structures. Free crystalline silica (α-Quartz) may be a component in ceiling tiles and gypsum board. Silica (including free crystalline silica) may also be a component of concrete and brick surfaces noted in the building.

Exposure to airborne silica is regulated under Ontario Regulation 490/09, *Designated Substances* - made under the Occupational Health and Safety Act.

## **Polychlorinated Biphenyls (PCBs)**

### *Background Information on PCBs*

Polychlorinated Biphenyls (PCBs) were commonly used as a dielectric insulating fluid in electrical equipment such as transformers, capacitors, and fluorescent and HID lamp ballasts. The production of PCBs in North America started in 1929 and was banned at the beginning of 1979. After 1981, no manufacturers produced fluorescent and HID lamps with PCB-containing ballasts.

PCBs are not designated substances under the Occupational Health and Safety Act.

### *PCB Regulations (SOR/2008-273)*

The *PCB Regulations* (the Regulations) set specific deadlines for ending the use of PCBs in concentrations at or above 50 mg/kg, eliminating all PCBs and equipment containing PCBs currently in storage and limiting the time PCBs can be stored before being destroyed. The Regulations also establish sound practices for the better management of the remaining PCBs in use (i.e. those with a content of less than 50 mg/kg) until their eventual elimination to prevent contamination of dielectric fluids and dispersion of PCBs in small quantities into other liquids.

## **Ozone Depleting Substances (ODSs) and Other Halocarbons**

### *Background Information on ODSs*

Within Ontario, the general use of ozone-depleting substances (ODSs) and other halocarbons is controlled through Regulation 463/10 of the Environmental Protection Act. The production of ODSs in hydrochlorofluorocarbons (HCFCs) and chlorofluorocarbons (CFCs) ceased in Canada in 1993 due to their ozone-depleting characteristics. The importation of CFCs into Canada ceased in 1997, and a total ban was placed on their use in 2010. The use of these materials is still permitted in existing equipment, but equipment must be serviced by a licensed contractor such that CFCs are contained and not released to the environment during servicing or operation.

## **Radioactive Materials**

Two types of smoke detectors are common in buildings (residential, institutional, commercial, industrial, etc). Photoelectric-type smoke detectors detect smoke using an optical sensor, whereas ionization-type smoke detectors use an ionization chamber containing radioactive material. The ionization type is cheaper and is particularly common in older buildings. A typical modern detector contains about 1.0 microcurie of the radioactive element americium, a decrease from 3 microcurie in 1978. The use of sealed radioactive material sources in fire detection systems is still permitted and regulated by the Canadian Nuclear Safety Commission and the Canadian Nuclear Safety Act. The radioactive sources in smoke alarms are sealed and contained within a metal case inside the smoke detector and must not be damaged or tampered with.

## Mould & Water Damage

Mould growth inside buildings is due to excess moisture caused by leakages, condensation or capillary movement of water into the building. Toxic moulds such as *Stachybotrys chartarum* and some species of *Aspergillus* spp. are greenish-black, wet and slimy moulds that grow on soaking, wet cellulose-based materials. They are often found near water leaks or where drying is very slow and can form after flooding if insufficient cleanup and drying occur. They will generally not occur if materials are kept dry.

MPL conducted a general visual assessment for any apparent signs of visible mould and/or water damage. Based on our visual observations, the following guidelines were used in providing our recommendations for remedial action where required:

- Institute of Inspection Cleaning and Restoration Certification (IICRC) S520 Standard and Reference for Professional Mould Remediation,
- The Canadian Construction Association (CCA) Mould Guidelines for the Canadian construction industry (CCA document 82-2004)
- Environmental Abatement Council of Canada (EACC) Mould Abatement Guidelines.

## Other Designated Substances

*Select Designated Substances (acrylonitrile, arsenic, coke oven emissions, ethylene oxide, isocyanates, benzene, or vinyl chloride) are not expected to be present in the building in the matrix or sufficient quantities to cause an exceedance of Ministry of Labour exposure guidelines. As such, no sampling was conducted for these materials.*

### Vinyl Chloride

Vinyl chloride (monomer) is likely to be present in stable form within poly vinyl-chloride (PVC) piping and conduits and as a component of interior finishes. Such building materials are not considered hazardous in their current matrix/composition.

### Acrylonitrile

Acrylonitrile or ACN (vinyl cyanide) is an explosive, flammable liquid used to manufacture acrylic fibres, rubber-like materials and pesticide fumigants. Acrylonitrile was not noted and would not be expected to be present in the project-specific area/surveyed area/subject building.

### Arsenic

Arsenic is used in metallurgy for hardening copper, lead and alloys, in pigment production, in the manufacture of certain types of glass, in insecticides, fungicides and rodenticides, as a by-product in the smelting of copper ores, and as a dopant material in semiconductor manufacturing. Arsenic or arsenic compounds were not noted nor expected to be present in the project-specific area/surveyed area/subject building.

## Benzene

Benzene or benzol is a colourless liquid. It is used as an intermediate in producing styrene, phenol, cyclohexane, and other organic chemicals and in manufacturing detergents, pesticides, solvents, and paint removers. It is also found in gasoline. Benzene may be present in stable form in roofing materials, paints and adhesives located throughout the subject building. Such building materials are not considered hazardous in their current matrix/composition.

## Coke Oven Emissions

Coke oven emission is a benzene-soluble fraction of the total particulate matter of the substances emitted into the atmosphere from metallurgical coke ovens.

## Ethylene Oxides

Ethylene oxide is a colourless gas liquefying below 12°C. It is generally used as a fumigant and sterilizing agent for medical equipment. It is generally used as a fumigant and sterilizing agent for medical equipment.

## Isocyanates

Isocyanate compounds may be present to stabilize paint finishes, varnishes, polyurethane plastics, synthetic rubbers, foams and adhesives. Such building materials are not considered hazardous in their current matrix/composition.

**To reduce the potential for exposure to workers or occupants, any suspect hazardous building material(s) not detailed within this survey due to inaccessibility and/or discovered during renovation/demolition activities must be appropriately assessed and/or tested prior to their disturbance.**

## **APPENDIX C**

### **Laboratory Analytical Reports**





# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
 Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672000324  
 Customer ID: 55CTCS25B  
 Customer PO: 0Z2-021101  
 Project ID: Ottawa DSS

**Attn:** John Tufts  
 McIntosh Perry Consulting Engineers Ltd  
 115 Walgreen Rd RR 3  
 Carp, ON K0A 1L0

**Phone:** (613) 836-2184  
**Fax:**  
**Collected:**  
**Received:** 2/14/2020  
**Analyzed:** 2/24/2020

**Proj:** University of Ottawa 0Z2-021101 (40 Stewart) (Ottawa DSS)

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

**Client Sample ID:** 1.1 **Lab Sample ID:** 672000324-0001

**Sample Description:** 40 Stewart/Carpet Mastic Rm 103

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Yellow	0.0%	100.0%	None Detected	

**Client Sample ID:** 1.2 **Lab Sample ID:** 672000324-0002

**Sample Description:** 40 Stewart/Carpet Mastic Rm 103

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Yellow	0.0%	100.0%	None Detected	

**Client Sample ID:** 1.3 **Lab Sample ID:** 672000324-0003

**Sample Description:** 40 Stewart/Carpet Mastic Rm 103

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	Yellow	0.0%	100.0%	None Detected	

**Client Sample ID:** 2.1 **Lab Sample ID:** 672000324-0004

**Sample Description:** 40 Stewart/Black Mastic B01

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Black	0.0%	90.0%	10% Chrysotile	

**Client Sample ID:** 2.2 **Lab Sample ID:** 672000324-0005

**Sample Description:** 40 Stewart/Black Mastic B01

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020					Positive Stop (Not Analyzed)

**Client Sample ID:** 2.3 **Lab Sample ID:** 672000324-0006

**Sample Description:** 40 Stewart/Black Mastic B01

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020					Positive Stop (Not Analyzed)

**Client Sample ID:** 3.1-Vinyl Sheet Flooring **Lab Sample ID:** 672000324-0007

**Sample Description:** 40 Stewart/Green VSF 203

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Green	10.0%	90.0%	None Detected	



# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672000324  
Customer ID: 55CTCS25B  
Customer PO: 0Z2-021101  
Project ID: Ottawa DSS

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

**Client Sample ID:** 3.1-Mastic **Lab Sample ID:** 672000324-0007A  
**Sample Description:** 40 Stewart/Green VSF 203

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Beige	5.0%	95.0%	None Detected	

**Client Sample ID:** 3.2-Vinyl Sheet Flooring **Lab Sample ID:** 672000324-0008  
**Sample Description:** 40 Stewart/Green VSF 203

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Green	10.0%	90.0%	None Detected	

**Client Sample ID:** 3.2-Mastic **Lab Sample ID:** 672000324-0008A  
**Sample Description:** 40 Stewart/Green VSF 203

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Beige	5.0%	95.0%	None Detected	

**Client Sample ID:** 3.3-Vinyl Sheet Flooring **Lab Sample ID:** 672000324-0009  
**Sample Description:** 40 Stewart/Green VSF 203

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	Green	13.0%	87.0%	None Detected	

**Client Sample ID:** 3.3-Mastic **Lab Sample ID:** 672000324-0009A  
**Sample Description:** 40 Stewart/Green VSF 203

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	Beige	5.0%	95.0%	None Detected	

**Client Sample ID:** 4.1 **Lab Sample ID:** 672000324-0010  
**Sample Description:** 40 Stewart/Drywall Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 4.2 **Lab Sample ID:** 672000324-0011  
**Sample Description:** 40 Stewart/Drywall Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 4.3-Joint Compound **Lab Sample ID:** 672000324-0012  
**Sample Description:** 40 Stewart/Drywall Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	White	0.0%	100.0%	None Detected	



# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672000324  
Customer ID: 55CTCS25B  
Customer PO: 0Z2-021101  
Project ID: Ottawa DSS

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

**Client Sample ID:** 4.3-Plaster **Lab Sample ID:** 672000324-0012A  
**Sample Description:** 40 Stewart/Drywall Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray/White	0.0%	100.0%	None Detected	

**Client Sample ID:** 4.4 **Lab Sample ID:** 672000324-0013  
**Sample Description:** 40 Stewart/Drywall Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 4.5-Joint Compound **Lab Sample ID:** 672000324-0014  
**Sample Description:** 40 Stewart/Drywall Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 4.5-Skim Coat **Lab Sample ID:** 672000324-0014A  
**Sample Description:** 40 Stewart/Drywall Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 4.5-Base Coat **Lab Sample ID:** 672000324-0014B  
**Sample Description:** 40 Stewart/Drywall Joint Compound

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	Gray	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.1-Skim Coat **Lab Sample ID:** 672000324-0015  
**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.1-Base Coat **Lab Sample ID:** 672000324-0015A  
**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray	2.0%	98.0%	None Detected	

**Client Sample ID:** 5.2-Skim Coat **Lab Sample ID:** 672000324-0016  
**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray/White	0.0%	100.0%	None Detected	



# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
 Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672000324  
 Customer ID: 55CTCS25B  
 Customer PO: 0Z2-021101  
 Project ID: Ottawa DSS

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

**Client Sample ID:** 5.2-Base Coat

**Lab Sample ID:** 672000324-0016A

**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.3-Skim Coat

**Lab Sample ID:** 672000324-0017

**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray/White	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.3-Base Coat

**Lab Sample ID:** 672000324-0017A

**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.4

**Lab Sample ID:** 672000324-0018

**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray/White	4.0%	96.0%	None Detected	Inseparable layers

**Client Sample ID:** 5.5-Skim Coat

**Lab Sample ID:** 672000324-0019

**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray/White	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.5-Base Coat

**Lab Sample ID:** 672000324-0019A

**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/21/2020	Gray	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.6-Joint Compound

**Lab Sample ID:** 672000324-0020

**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.6-Skim Coat

**Lab Sample ID:** 672000324-0020A

**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	White	0.0%	100.0%	None Detected	



# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672000324  
Customer ID: 55CTCS25B  
Customer PO: 0Z2-021101  
Project ID: Ottawa DSS

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

**Client Sample ID:** 5.6-Base Coat **Lab Sample ID:** 672000324-0020B  
**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	Gray	1.0%	99.0%	None Detected	

**Client Sample ID:** 5.7-Joint Compound **Lab Sample ID:** 672000324-0021  
**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.7-Skim Coat **Lab Sample ID:** 672000324-0021A  
**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	White	0.0%	100.0%	None Detected	

**Client Sample ID:** 5.7-Base Coat **Lab Sample ID:** 672000324-0021B  
**Sample Description:** 40 Stewart/Plaster

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	2/24/2020	Gray	1.0%	99.0%	None Detected	

**Analyst(s):**  
Ewa Krupinska PLM (12)  
Simon Parent PLM (21)

**Reviewed and approved by:**   
Simon Parent, Laboratory Manager  
or Other Approved Signatory

None Detected = <0.1%. EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported above and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. Samples received in good condition unless otherwise noted. This report must not be used to claim product endorsement by NVLAP of any agency or the U.S. Government

Samples analyzed by EMSL Canada Inc. Ottawa, ON

Initial report from: 02/24/2020 15:38:36



# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
 Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672201278  
 Customer ID: 55CTCS25B  
 Customer PO: CCC-230252-00  
 Project ID:

**Attn:** Lauren Hamilton Phone: (613) 836-2184  
 McIntosh Perry Consulting Engineers Ltd Fax:  
 115 Walgreen Rd RR 3 Collected:  
 Carp, ON K0A 1L0 Received: 7/05/2022  
 Analyzed: 7/12/2022

**Proj:** UO Reassessments

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

**Client Sample ID:** BS-66temp-1 **Lab Sample ID:** 672201278-0001

**Sample Description:** 102/Ceiling Texture Coat

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	White	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-66temp-2 **Lab Sample ID:** 672201278-0002

**Sample Description:** 103/Ceiling T.C

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	White	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-66temp-3 **Lab Sample ID:** 672201278-0003

**Sample Description:** B2/Ceiling T.C

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	White	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-66temp-4 **Lab Sample ID:** 672201278-0004

**Sample Description:** B2/Ceiling T.C

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	White	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-66temp-5 **Lab Sample ID:** 672201278-0005

**Sample Description:** B3/Ceiling T.C

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/12/2022	White	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-76temp-1-Vinyl Floor Tile **Lab Sample ID:** 672201278-0006

**Sample Description:** VFT - beige w/ brown specs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	Brown/Beige	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-76temp-1-Mastic **Lab Sample ID:** 672201278-0006A

**Sample Description:** VFT - beige w/ brown specs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022				Insufficient Material	



# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672201278  
Customer ID: 55CTCS25B  
Customer PO: CCC-230252-00  
Project ID:

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

**Client Sample ID:** BS-76temp-2-Vinyl Floor Tile **Lab Sample ID:** 672201278-0007

**Sample Description:** 2nd floor bedroom/VFT - beige w/ brown specs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	Brown/Beige	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-76temp-2-Mastic **Lab Sample ID:** 672201278-0007A

**Sample Description:** 2nd floor bedroom/VFT - beige w/ brown specs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	Black	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-76temp-3-Vinyl Floor Tile **Lab Sample ID:** 672201278-0008

**Sample Description:** 2nd floor bedroom/VFT - beige w/ brown specs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/12/2022	Brown/Beige	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-76temp-3-Mastic **Lab Sample ID:** 672201278-0008A

**Sample Description:** 2nd floor bedroom/VFT - beige w/ brown specs

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/12/2022	Black	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-80temp-1-Vinyl Floor Tile **Lab Sample ID:** 672201278-0009

**Sample Description:** VFT - yellow

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	Yellow	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-80temp-1-Mastic **Lab Sample ID:** 672201278-0009A

**Sample Description:** VFT - yellow

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	Black	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-80temp-2-Vinyl Floor Tile **Lab Sample ID:** 672201278-0010

**Sample Description:** VFT - yellow

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	Yellow	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-80temp-2-Mastic **Lab Sample ID:** 672201278-0010A

**Sample Description:** VFT - yellow

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	Black	0.0%	100.0%	None Detected	



# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672201278  
Customer ID: 55CTCS25B  
Customer PO: CCC-230252-00  
Project ID:

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

**Client Sample ID:** BS-80temp-3-Vinyl Floor Tile **Lab Sample ID:** 672201278-0011  
**Sample Description:** VFT - yellow

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/12/2022	Yellow	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-80temp-3-Mastic **Lab Sample ID:** 672201278-0011A  
**Sample Description:** VFT - yellow

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/12/2022	Black	0.0%	100.0%	None Detected	

**Client Sample ID:** BS-40Ste-1 **Lab Sample ID:** 672201278-0012  
**Sample Description:** Basement/Paper duct insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022	Gray	0.0%	35.0%	65% Chrysotile	

**Client Sample ID:** BS-40Ste-2 **Lab Sample ID:** 672201278-0013  
**Sample Description:** Basement/Paper duct insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022					Positive Stop (Not Analyzed)

**Client Sample ID:** BS-40Ste-3 **Lab Sample ID:** 672201278-0014  
**Sample Description:** Basement/Paper duct insulation

TEST	Analyzed Date	Color	Non-Asbestos		Asbestos	Comment
			Fibrous	Non-Fibrous		
PLM	7/11/2022					Positive Stop (Not Analyzed)





# EMSL Canada Inc.

22 Antares Drive Suite 102 Ottawa, ON K2E 7Z6  
Phone/Fax: (343) 882-6076 / (343) 882-6077  
<http://www.EMSL.com> / [ottawalab@EMSL.com](mailto:ottawalab@EMSL.com)

EMSL Canada Order 672201278  
Customer ID: 55CTCS25B  
Customer PO: CCC-230252-00  
Project ID:

## Test Report: Asbestos Analysis of Bulk Materials for Ontario Regulation 278/05 via EPA600/R-93/116 Method

---

### Analyst(s):

---

Brianne Bedard PLM (5)  
Simon Parent PLM (12)

### Reviewed and approved by:

Ewa Krupinska, Laboratory Manager  
or Other Approved Signatory

None Detected = <0.1%. EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. Results are generated from the field sampling data (sampling volumes and areas, locations, etc.) provided by the client on the Chain of Custody. Samples are within quality control criteria and met method specifications unless otherwise noted. Estimation of uncertainty available upon request. This report is a summary of multiple methods of analysis, fully compliant reports are available upon request. A combination of PLM and TEM analysis may be necessary to ensure consistently reliable detection of asbestos. This report must not be used to claim product endorsement by NVLAP of any agency or the U.S. Government.

Samples analyzed by EMSL Canada Inc. Ottawa, ON NVLAP Lab Code 201040-0

Initial report from: 07/12/2022 10:01:50

**EMSL Canada Inc.**

2756 Slough Street, Mississauga, ON L4T 1G3

Phone/Fax: (289) 997-4602 / (289) 997-4607

<http://www.EMSL.com>[torontolab@emsl.com](mailto:torontolab@emsl.com)

EMSL Canada Or	552001887
CustomerID:	55CTCS25B
CustomerPO:	0Z2-021101
ProjectID:	

Attn: **John Tufts**  
**McIntosh Perry Consulting Engineers Ltd**  
**115 Walgreen Rd RR 3**  
**Carp, ON K0A 1L0**

Phone: (613) 836-2184  
 Fax:  
 Received: 02/18/20 11:41 AM  
 Collected:

Project: **UofIO Ottawa DSS****Test Report: Lead in Paint Chips by Flame AAS (SW 846 3050B/7000B)\***

<i>Client SampleDescription</i>	<i>Collected</i>	<i>Analyzed</i>	<i>Weight</i>	<i>RDL</i>	<i>Lead Concentration</i>
PB1 552001887-0006		2/19/2020	0.1057 g	0.019 % wt	0.12 % wt
	Site: 40 Stewart, Green Door				
PB2 552001887-0007		2/19/2020	0.2045 g	0.98 % wt	22 % wt
	Site: 40 Stewart, Dark Green Door				
PB3 552001887-0008		2/19/2020	0.2508 g	0.0080 % wt	0.12 % wt
	Site: 40 Stewart, 203C, Light Blue				
PB4 552001887-0009		2/19/2020	0.2441 g	0.41 % wt	7.7 % wt
	Site: 40 Stewart, 209, Light Green				
PB5 552001887-0010		2/19/2020	0.2494 g	0.0080 % wt	0.20 % wt
	Site: 40 Stewart, 105, White				
PB6 552001887-0011		2/19/2020	0.2499 g	0.16 % wt	5.4 % wt
	Site: 40 Stewart, 102, Beige				
PB7 552001887-0012		2/19/2020	0.2304 g	0.43 % wt	10 % wt
	Site: 40 Stewart, Deck, Grey				


Rowena Fanto, Lead Supervisor  
 or other approved signatory

\*Analysis following Lead in Paint by EMSL SOP/Determination of Environmental Lead by FLAA. Reporting limit is 0.008 % wt based on the minimum sample weight per our SOP. Unless noted, results in this report are not blank corrected. EMSL maintains liability limited to cost of analysis. Interpretation and use of test results are the responsibility of the client. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. The report reflects the samples as received. When the information supplied by the customer can affect the validity of the results, it will be noted on the report. "<" (less than) result signifies the analyte was not detected at or above the reporting limit. Measurement of uncertainty is available upon request. The QC data associated with the sample results included in this report meet the recovery and precision requirements unless specifically indicated otherwise. Definitions of modifications are available upon request.

Samples analyzed by EMSL Canada Inc. Mississauga, ON AIHA-LAP, LLC - ELLAP #196142

Report Amended: 03/06/2020 08:42:11 Replaces the Initial Report 02/25/2020 08:47:17. Reason Code: Client-Change to Appearance

**APPENDIX D**  
**Site Photographs**



**Photo 1:** Typical view of basement finishes.



**Photo 2:** View of asbestos-containing black mastic **containing 10% Chrysotile** on basement window plywood.



**Photo 3:** View of asbestos-containing duct insulation paper **containing 10% Chrysotile** in the basement.



**Photo 4:** Typical view of the main floor finishes.



**Photo 5:** View on non-asbestos carpet mastic (yellow) on the main floor.



**Photo 6:** Typical new non-asbestos wall and ceiling plaster on the first floor and stairwell.



**Photo 7:** View of non-asbestos vinyl sheet flooring (blue-green) observed in room 203C.



**Photo 8:** View of lead-containing white paint observed on the wall in Room 105.




**Photo 9:** View of lead-containing beige paint observed on the ceiling in Room 102.



**Photo 10:** View of lead-containing green paint observed on the door of Room 101.



**Photo 11:** View of lead-containing light blue paint observed on the door of Room 203C



**Photo 12:** View of lead-containing light green paint observed on the wall in Room 206.



**Photo 13:** View of lead-containing dark green paint observed on the doorframe of Room 206.



**Photo 14:** View of lead-containing beige paint on ceiling and white paint on the piping observed to be in poor condition in Room 105.






**Photo 15:** View of lead-containing blue paint on walls observed to be in poor condition in Room 205.



**Photo 16:** View of radioactive-containing smoke detector observed in Room B3.



**Photo 17:** View of non-PCB containing Sylvania light ballast observed in Room 105.



**Photo 18:** View of Above-ground Storage Tank (AST) observed to be present in the basement.

## **APPENDIX E**

### **Asbestos-Containing Materials Checklists**

Floor/Level	Room	ID	Type of ACM	Description	Asbestos Confirmed/ Suspected	Friable/Non-Friable	Damaged/ Deteriorated	Accessibility	Level of Work Near Material	Approx. Quantity	Unit	Recommended Action	Estimated Abatement Cost	Comment
1	Room	01	Brick/Stone Mortar	Grey	Suspected	-	Good Condition	Easy	Low	-	-	Manage in Place	-	
1	Room	01	Mastic	Black	Confirmed	Non-Friable	Fair Condition	Easy	Low	5	SF	Monitor Condition of Material. Consider Removal or Repair.	-	
1	Room	01	Duct Paper Insulation	N/A	Confirmed	Non-Friable	Fair Condition	Easy	Low	5	SF	Monitor Condition of Material. Consider Removal or Repair.	-	

## **APPENDIX F**

### **Hazardous Containing Materials Checklists**

Floor/Level	Location	ID	DS Type	Component	Colour	Condition	Manufacturer	Quantity #	Unit	Suspected/ Confirmed	Recommended Action	Estimated Abatement Cost	Comments
1	Exterior	-	Lead	Floor Paint	Grey	Poor Condition	N/A	50	SF	Confirmed	Paint must be removed and/or stabilized following Class 1/2 or Type 1/2 Lead Procedures as per MOL and EACC Guidelines.	\$500.00	
1	Room	102	Ozone Depleting Substances (ODS)	Air Conditioning Unit	N/A	Good Condition	Comfort Air	1	C	Confirmed	Manage in Place		Unknown Refrigerant
1	Room	105	Lead	Wall Paint	White	Good Condition	N/A	-	-	Confirmed	Manage in Place		
1	Room	105	Ozone Depleting Substances (ODS)	Air Conditioning Unit	N/A	Good Condition	Friedrich	1	C	Confirmed	Manage in Place		Unknown Refrigerant
2	Room	201	Ozone Depleting Substances (ODS)	Air Conditioning Unit	N/A	Good Condition	Friedrich	1	C	Confirmed	Manage in Place		Unknown Refrigerant
1	Room	105	Lead	Wall Paint	White	Good Condition	N/A	-	-	Confirmed	Manage in Place		
1	Room	105	Lead	Ceiling Paint	Beige	Poor Condition	N/A	3	SF	Confirmed	Paint must be removed and/or stabilized following Class 1/2 or Type 1/2 lead Procedures as per MOL and EACC Guidelines.		

Floor/Level	Location	ID	DS Type	Component	Colour	Condition	Manufacturer	Quantity #	Unit	Suspected/ Confirmed	Recommended Action	Estimated Abatement Cost	Comments
1	Room	105	Lead	Pipe Paint	White	Poor Condition	N/A	6	LF	Confirmed	Paint must be removed and/or stabilized following Class 1/2 or Type 1/2 lead Procedures as per MOL and EACC Guidelines.		
1	Room	102	Lead	Ceiling	Beige	Good Condition	N/A	-	-	Confirmed	Manage in Place		
1	Room	101	Lead	Door	Green	Good Condition	N/A	-	-	Confirmed	Manage in Place		
2	Room	206	Ozone Depleting Substances (ODS)	Air Conditioning Unit	Brown	Fair Condition	Diplomat	1	C	Confirmed	Manage in Place		R-12
2	Room	200	Ozone Depleting Substances (ODS)	Air Conditioning Unit		Good Condition	Diplomat	1	C	Confirmed	Manage in Place		R-12
1	Exterior Porch	-	Lead	Floor Paint	Grey	Poor Condition	N/A	100	SF	Confirmed	Paint must be removed and/or stabilized following Class 1/2 or Type 1/2 Lead Procedures as per MOL and EACC Guidelines.	\$2,000.00	
2	Room	206	Lead	Wall Paint	Light Green	Good Condition	N/A	-	-	Confirmed	Manage in Place		
2	Room	203C	Lead	Wall Paint	Light Blue	Good Condition	N/A	-	-	Confirmed	Manage in Place		


Floor/Level	Location	ID	DS Type	Component	Colour	Condition	Manufacturer	Quantity #	Unit	Suspected/ Confirmed	Recommended Action	Estimated Abatement Cost	Comments
2	Room	205	Lead	Wall Paint	Blue	Poor Condition	N/A	10	SF	Confirmed	Paint must be removed and/or stabilized following Class 1/2 or Type 1/2 Lead Procedures as per MOL and EACC Guidelines.		
2	Room	206	Lead	Wall Paint	Light Green	Good Condition	N/A	-	-	Confirmed	Manage in Place		
1	Room	105	Lead	Battery Pack	N/A	Good Condition	N/A	1	C	Confirmed	Manage in Place		
2	Room	206	Lead	Wall Paint	Dark Green	Good Condition	N/A	-	-	Confirmed	Manage in Place		
All	Throughout Subject Building	-	Mercury	Fluorescent Light Tubes	N/A	Good Condition	N/A	-	-	Confirmed	Manage in Place		
1	Room	200	Radioactive Materials	Smoke Detectors	N/A	Good Condition	Unknown	1	C	Confirmed	Manage in Place		
0	Room	B3	Radioactive Materials	Smoke Detectors	N/A	Good Condition	Unknown	1	C	Confirmed	Manage in Place		
All	Throughout Subject Building	-	Silica	Concrete, Mortar, Etc.	N/A	Good Condition	N/A	-	-	Confirmed	Manage in Place		
B	Basement	-	USTs/ASTs	Diesel Storage Tank	N/A	Good Condition	N/A	2	C	Confirmed	Manage in Place		Above Ground Storage Tank (AST)



## **APPENDIX G**

### **Site Sampling & Location Plans**

C:\USERS\S.REZAEIAN\DESKTOP\HAZMAT\SHAHIN\DRAWINGS USED IN REPORTS\112-DWG - SAMPLE LOCATION - 40 STEWART.DWG



# McINTOSH PERRY

6240 HIGHWAY 7 SUITE 200 WOODBRIDGE ON L4H 4G3  
 Tel: 905.856.5200 Fax: 905.695.0221  
 Toll Free: 1.888.348.8991 www.mcintoshperry.com

THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS.  
 REPORT ALL ERRORS AND OMISSIONS TO THE CONSULTANTS, PRIOR  
 TO PROCEEDING WITH ANY WORKS.

**Legend:**

- ▲ Asbestos Bulk Sample
- Lead Paint Sample <LOD
- Lead Paint Sample >LOD

ACM Caulking & Mastic

CLIENT: UNIVERSITY OF OTTAWA


PROJECT: HAZARDOUS MATERIALS SURVEY  
 40 STEWART, OTTAWA, ONTARIO

TITLE: MASTER DRAWING  
 LEVEL 00  
 SAMPLE LOCATION

SCALE: 1:50  
 DATE: JUNE 2, 2020  
 DRAWN: S.G.  
 CHECKED: M.M.

REV. NO.	DESCRIPTION	DATE	BY	APPD.

DRAWING NUMBER: A-00



C:\USERS\DIANA\DESKTOP\UNIVERSITY OF OTTAWA - 85 BUILDINGS\BATCH 1 DRAWINGS\0 STEWART\0 STEWART.DWG

**McINTOSH PERRY**  
 6240 HIGHWAY 7 SUITE 200 WOODBRIDGE ON L4H 4G3  
 Tel: 905.856.5200 Fax: 905.695.0221  
 Toll Free: 1.888.348.8991 www.mcintoshperry.com

- Legend:**
- ▲ Asbestos Bulk Sample
  - Lead Paint Sample <LOD
  - Lead Paint Sample >LOD


THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS, REPORT ALL ERRORS AND OMISSIONS TO THE CONSULTANTS, PRIOR TO PROCEEDING WITH ANY WORKS.

CLIENT: UNIVERSITY OF OTTAWA  
 PROJECT: HAZARDOUS MATERIALS SURVEY  
 40 STEWART, OTTAWA, ONTARIO

TITLE: MASTER DRAWING  
 LEVEL 01  
 SAMPLE LOCATION  
 SCALE: 1:50  
 DATE: JUNE 2, 2020  
 DRAWN: S.G.  
 CHECKED: M.M.

REV. NO.	DESCRIPTION	DATE	BY	APPD.

DRAWING NUMBER: A-01



**McINTOSH PERRY**  
 6240 HIGHWAY 7 SUITE 200 WOODBRIDGE ON L4H 4G3  
 Tel: 905.856.5200 Fax: 905.695.0221  
 Toll Free: 1.888.348.8991 www.mcintoshperry.com

- Legend:**
- ▲ Asbestos Bulk Sample
  - Lead Paint Sample <LOD
  - Lead Paint Sample >LOD

THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS, REPORT ALL ERRORS AND OMISSIONS TO THE CONSULTANTS, PRIOR TO PROCEEDING WITH ANY WORKS.

CLIENT: UNIVERSITY OF OTTAWA

TITLE: MASTER DRAWING  
 LEVEL 02  
 SAMPLE LOCATION


PROJECT: HAZARDOUS MATERIALS SURVEY  
 40 STEWART, OTTAWA, ONTARIO

SCALE: 1:50  
 DATE: JUNE 2, 2020  
 DRAWN: S.G.  
 CHECKED: M.M.

REV. NO.	DESCRIPTION	DATE	BY	APPD.

DRAWING NUMBER: A-02

C:\USERS\DIANA\DESKTOP\UNIVERSITY OF OTTAWA - 85 BUILDINGS\BATCH 1 DRAWINGS\0 STEWART\0 STEWART.DWG



**McINTOSH PERRY**  
 6240 HIGHWAY 7 SUITE 200 WOODBRIDGE ON L4H 4G3  
 Tel: 905.856.5200 Fax: 905.695.0221  
 Toll Free: 1.888.348.8991 www.mcintoshperry.com

- Legend:**
- ▲ Asbestos Bulk Sample
  - Lead Paint Sample <LOD
  - Lead Paint Sample >LOD

THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS,  
 REPORT ALL ERRORS AND OMISSIONS TO THE CONSULTANTS, PRIOR  
 TO PROCEEDING WITH ANY WORKS.

CLIENT: UNIVERSITY OF OTTAWA

TITLE: MASTER DRAWING  
 LEVEL 03  
 SAMPLE LOCATION

PROJECT: HAZARDOUS MATERIALS SURVEY  
 40 STEWART, OTTAWA, ONTARIO

SCALE: 1:50 DATE: JUNE 2, 2020  
 DRAWN: S.G. CHECKED: M.M.

REV. NO.	DESCRIPTION	DATE	BY	APPD.

DRAWING NUMBER: A-03

C:\USERS\DIANA\DESKTOP\UNIVERSITY OF OTTAWA - 85 BUILDINGS\BATCH 1 DRAWINGS\40 STEWART\40 STEWART.DWG